

PETROPROD 1 FPSO PROJECT UPDATE

The PetroProd 1 FPSO has begun conversion works at Jurong Shipyard, Singapore. The process topside modules, internal mooring system and power generation units (21MW) will be integrated onto the FPSO and completed for sailaway by 4Q 2008.

Engineering, Procurement, Construction and Commissioning phase is managed by Larsen Oil and Gas Pte Ltd (Singapore).



PETROPROD 1 FPSO: Available for lease from 4Q 2008.

PETROPROD 1 FPSO General Specifications			
Vessel Name	PetroProd 1 FPSO	Mooring Type	Internal Mooring System - 9 mooring lines - Up to 10 Riser and 8 Umbilical - 70m to 1,000m water depth
New/Conversion	Conversion – Double Sided Aframax		
Dwt	105,383	Process	Production: 60,000bpd
Dimension	244.5m x 42.6m x 19.8m	Gas Injection	Gas Treatment: 80mmscfd Gas Injection: 67 mmscfd
Classification	Lloyds Register	Water Injection	80,000bwpd
	OI 100AT(1) Floating Production and Oil Storage Installation	Produced Water Treatment	50,000bpd

- **Look out for project progression picture updates (vessel conversion, topside process modules, etc) that will be available shortly.**